

STEP 1: INSTALL THE HARDWARE

Step 1

Remove retainer screw from panel top



Step 2

Pull back plate off gently




Step 3

Mount back plate to wall

Step 8



Hook panel stabilizer strap onto back plate



Connect battery DO NOT DISCONNECT AFTER INSTALLATION

Step 6



Connect wires. DCIN+ to Positive DCIN- to Negative



Positive to +

Negative to -



Connect power supply



Plug in power supply and secure with screw. Flip bracket upside for decor style plugs.



Tilt panel upward onto back plate until it snaps in place



Replace retainer screw and tighten

STEP 2: CONNECT WI-FI







Wireless Settings

Touch "Wireless Settings"

Wi-Fi Settings Select network

Touch "Wi-Fi Settings"

Select the desired network.

> Enter Wi-Fi password if required.

*Requires Installer code, default is "1111"

STEP 3: RUN A CELL TEST

System

Tests



Settings





Cellular Test Start Cancel

Touch "Start" to begin the test

Cellular radio test started. Please walt... Cellular wireless bath tested successfully. Call Central Station to check reports if needed.

Successful results will initiate a panel download from the Alarm.com servers, like date, local time, weather, etc., and begins syncing your company's contact info & template settings. Alarm.com account must be created prior to test.

STEP 4: CHECK FOR SOFTWARE UPDATES



Settings



Installation



Upgrade Software

Upgrade Using Network Search network for updates and install new software

Touch "Upgrade using Network"

NOTE: Download could take could take up to 3 minutes, depending on your connection speed. After the panel re-starts DO NOT TOUCH THE PANEL for 5 minutes to allow the software to fully install. If update is available it will download and install automatically. Once complete, touch "OK" to restart the panel.

OK

STEP 5: PAIR SECURITY & LIFE SAFETY SENSORS



Settings









'Tamper'' Sensor Typically done by opening case, see manual for specifics

Add

Device

information

appears

automatically.

Edit as desired.



chime and a message will appear. Touch "OK"



Select a quick

name or custom.

Touch "Add"

Add

NOTE: Image Sensors are placed in "pairing mode" by removing and replacing the batteries. See installation manual for details.

STEP 6: PAIR Z-WAVE DEVICES







Left Socket

Right Socket Right Socket



Smart Socket



Home Control **Devices**



Touch "Pair" Device



The panel will begin "looking" for devices



Touch "Add" to complete the pairing process.

NOTE: If the device does not learn in you may need to "Clear Device" first. See installation manual for detailed steps

IMPORTANT

Press "Learn

button on

device

FOR DETAILED INSTRUCTIONS REFER TO THE IQ PANEL INSTALLATION MANUAL ON DEALERS.QOLSYS.COM

Security Signaling Residential Fire Alarm and **Security Equipment**

ETL Listed

Conforms to ANSI/UL Standards Conforms to ANSI/UL Std. S985. 1023. & 1635 Certified to ULC Sub. C1023 & ULC Std. S545

Document#: IQPANEL-QG-01-15 Revision Date: 5/1/15 Applies to Qolsys Part #s:

QS-9004-VRZ QS9014-124-00-04 QS9004-840-00-00 QS9014-484-00-06 QS9014-840-00-02







Qolsys Inc. proprietary. Reproduction without permission is not permitted.

ALL IN ONE. ALWAYS CONNECTED























There may be new features available for this IQ Panel.

After installation is complete follow the instructions inside for connecting to Wi-Fi and performing a software update.



